

DATE: 08/17/2021

CONTRACT SOLICITATION NOTICE/PROJECT OVERVIEW

MTA-C&D IS NOW ADVERTISING FOR THE FOLLOWING:

SSE EVENT#: 0000363792

OPENING/DUE DATE: 09/30/2021

TYPE OF SOLICITATION: IFB

DOCUMENT AVAILABILITY DATE: 08/17/2021

SOLICITATION TITLE: 106733 Hartsdale, Scarsdale and Purdy Station improvements

DESCRIPTION: The Metropolitan Transportation Authority ("MTA"), by and through its agent the MTA Construction & Development Company ("MTA C&D"), both of which are public benefit corporations existing by virtue of Article 5, Title 11 of the Public Authorities Law, will be issuing a Information for bidders ("IFB") seeking entities interested in the Hartsdale, Scarsdale and Purdy Station Improvements. This construction contract includes installation of 4 new elevators at 3 Harlem Line Stations (Hartsdale, Scarsdale and Purdy's). Hartsdale Station scope of work includes installation of 2 new elevators (inbound and outbound platforms). Scarsdale Station scope of work includes installation of 1 new elevator (inbound platform) and jacking of the existing pedestrian overpass to provide Plate E clearance. Purdy's Station scope of work includes demolition of existing stairs and installation of 1 new elevator on the north end of the parking lot, and sidewalk improvements to provide ADA access from the new elevator to the existing elevator at the station entrance. This project will provide improved accessibility at these stations. It is anticipated that the contract will be funded in whole or in part by NY State grants. This is an A+B type contract.

Funding: 100% Capital Goals: 15% MBE; 15% WBE; 6% SDVOB Est \$ Range: \$10M - \$50M Contract Term: 20 Months

*****PLEASE SEE THE ATTACHED FOR ADDITIONAL INFORMATION*****

() PRE-BID CONFERENCE LOCATION:	DATE:	TIME:
(X) SITE TOUR LOCATION:	DATE: 08/25/2021	TIME: 10:00AM
Scarsdale Station- 1 Depot Pl, Scarsdale NY 10583		

FOR MORE INFORMATION, PLEASE CONTACT:

PROCUREMENT REPRESENTATIVE: Jayesh Mehta **EMAIL:** Jayesh.mehta@mtacd.org

REQUIREMENTS TO PARTICIPATE

DATA UNIVERSAL NUMBERING SYSTEM (DUNS) NUMBER: ALL VENDORS MUST HAVE A DUN & BRADSTREET DUNS NUMBER IF THEY WISHTO PARTICIPATE IN THIS PROCUREMENT. VENDORS WHO DO NOT HAVE A DUNS NUMBER CAN REGISTER ONLINE AT WWW.MYDNC.COM. TO OBTAIN ONE FREE OF CHARGE. YOU MUST STATE THAT THE NUMBER IS REQUIRED FOR SAM (SYSTEM FOR AWARD MANAGEMENT)

SYSTEM FOR AWARD MANAGEMENT (SAM): VENDORS ARE ALSO REQUIRED TO REGISTER WITH SAM, A FEDERAL VENDOR DATABASE USED TO VALIDATE VEDNDOR INFORMATION, BEFORE REQUESTING BID DOCUMENTS. YOU CAN VISIT THEIR WEBSITE AT www.sam.gov TO REGISTER. A DUNS NUMBER IS REQUIRED FOR REGISTRATION.

*****WE CANNOT PROCESS DOCUMENT REQUESTS WITHOUT A MTA BIDDER/SUPPLIER NUMBER. PLEASE ACCESS THE MTA VENDOR PORTAL, WWW.MYMTA.INFO, TO REGISTER AS A BIDDER*****

Hartsdale, Scarsdale, & Purdy's Station Improvements – Elevators

MNR Contract# 1000106733

Summary of Work:

This contract covers, but is not limited to, furnish and installation of new elevators for three (3) Metro-North Stations on the Harlem Line: Hartsdale Station, Scarsdale Station, and Purdy's Station.

The scope of work at Hartsdale Station, located at Hartsdale, NY includes the following:

- Furnish and install two (2) new ADA elevators and all necessary components and equipment, including two (2) new enclosed elevator towers located on each platform side serving street level to platform level and overpass level.
- Install new elevator machine rooms to house equipment adjacent to elevators.
- Construct new ADA sidewalks from each elevator at street level.
- Construct an elevated walkway connecting the elevator tower to the existing overpass level.
- Install new benches, leaning bars, LED lighting and heaters to the existing overpass.
- The Contractor shall coordinate with Con Edison for the upgraded power as well as perform all additional electrical scope related to the elevators and existing overpass scope.

The scope of work at Scarsdale Station, located at Scarsdale, NY include the following:

- Furnish and install one (1) new ADA elevator, all necessary components and equipment, including one (1) new enclosed elevator tower serving street level, platform level and overpass level on the inbound platform side.
- Install one (1) elevator machine room to house equipment adjacent to elevator.
- Construct new ADA sidewalk from the elevator at street level.
- Raise (or jack) the existing passenger overpass structure and stair/stair enclosure structure to the inbound platform side by 7 inches to meet the required height from top of rail.
- Demolish existing communications CCTV bungalow on the inbound platform side and construct a new communications room adjacent to the elevator machine room for the relocation of the CCTV equipment. Repair/replace the connected utilities affected by relocation.
- Install new benches, leaning bars, new LED lighting and heaters to the existing overpass.
- Construct walkway connecting platform from elevator platform level landing to station platform and overpass.
- Construct motorcycle parking on street level.

The scope of work at Purdy's Station, located at Purdy's, NY, includes the following:

- Demolish the existing staircase, supports and foundations.
- Furnish and install one (1) new ADA elevator, all necessary components and equipment, including one (1) new enclosed elevator tower serving parking lot level and roadway above level on the north end of the parking lot.
- Install one (1) elevator machine room to house equipment adjacent to elevator.
- Construct an ADA compliant pathway(sidewalk) from the new elevator to the existing station entrance including LED lighting, utility relocation and parking lot modifications.
- Modification of fencing on roadway above level (Route 116).
- Install, inspect, and maintain Best Management Practices for sediment and erosion control in accordance with the latest revision of the New York State Standard Standards and Specifications for Erosion and Sediment Control.